

PLANNING COMMISSION REPORT
Regular Agenda – Public Hearing Item

PC Staff Report
11/17/14

**ITEM NO. 2 SPECIAL USE PERMIT FOR VERIZON WIRELESS; 1725 BULLENE AVE
(SLD)**

SUP-14-00312: Consider a Special Use Permit for a new 120' Verizon Wireless communications tower located at 1725 Bullene Ave. Submitted by PAMCORP LLC for Verizon Wireless LLC on behalf of Steven L. Eudaly, property owner of record.

STAFF RECOMMENDATION: Planning Staff recommends approval of a Special Use Permit for a communication tower located at 1725 Bullene Ave and forwarding the request to the City Commission with a recommendation of approval, subject to the following conditions:

1. Prior to release of the site plan for issuance of a building permit, the applicant shall provide the following changes and documentation:
 - a. Submission of documentation to demonstrate the tower fall zone will be maintained within the proposed enclosure area.
 - b. Submission of lighting details to show the fixture type, lamp type and size not to exceed 150 watt incandescent lighting, and cut-off feature to shield and direct light downward.
2. Provision of a revised site plan to include a landscape plan per City Staff approval that shows additional landscape to include evergreen shrubs planted 5' on center along the west half of the north property line to provide screening between the proposed tower and the abutting residential zoning to the north.

Applicant's Reason for Request: *"Verizon Wireless proposes to construct and operate a 120' tall self-supporting monopole type communications tower which will be used to provide enhanced wireless voice and data services to its local subscribers. The facility will be unmanned and will be designed to accommodate at least two additional sets of antenna for use by other carriers"*

ATTACHMENTS

1. Area Map
2. Site Plan
3. Photo Simulations
4. Search Ring Map
5. RF Engineer Letter
6. 3rd Party Review Structures Map

KEY POINTS

- Third party review found the applicant's burden of proof justifying the need for a new communication tower is met.

ASSOCIATED CASES/OTHER ACTION REQUIRED

- City Commission approval of Special Use Permit and adoption of ordinance.
- Publication of Special Use Permit ordinance.

PUBLIC COMMENT RECEIVED PRIOR TO PRINTING

- Questions from nearby residents requesting clarification of request.
- Neighborhood representative requested additional documents regarding reason and justification for request and inquired about proposed fencing.

Site Summary	
Subject Property:	27,510 SF
Proposed Buildings:	Irregular Lease area [generally 55' x 48'] 11 x 27' pad site for equipment shelter H frame for equipment 120' monopole Generator located within shelter building Additional pad sites for future carriers.

GENERAL INFORMATION	
Current Zoning and Land Use:	IL (Limited Industrial) District; existing office warehouse building.
Surrounding Zoning and Land Use:	RS5 (Single-Dwelling Residential) District to the north; vacant lot immediately north, existing residences along the west side of Bullene Avenue to the north.
	IL (Limited Industrial) District, RS7 (Single-Dwelling Residential) District, and PD-[Villow Woods Planned Residential Development] District to the west. Existing Burrough's Creek Trail and Linear Park.
	IG (General Industrial) District to the south. Existing Construction sales and services use.
	IG (General Industrial) District and IL (Limited Industrial) District to the east. Existing vacant warehouse use.

Summary of Request

This request is for the construction of a new 120' communication tower to include Verizon communication equipment. Additional space is available on the tower and within the ground lease area for other communication carriers in the future.

Review and Decision-Making Criteria (Land Development Code Section 20-1306(i))

1. WHETHER THE PROPOSED USE COMPLIES WITH ALL APPLICABLE PROVISIONS OF THIS DEVELOPMENT CODE

Applicant's Response: *"Yes"*.

Two key considerations of the application for a new communication tower are the compliance with Section 20-529 Telecommunication Facilities and completion of an independent third party review of the request. The proposed application complies with these requirements of the Development Code.

Staff Finding – This use complies with the applicable provisions of the Development Code.

2. WHETHER THE PROPOSED USE IS COMPATIBLE WITH ADJACENT USES IN TERMS OF SCALE, SITE DESIGN, AND OPERATING CHARACTERISTICS, INCLUDING

**HOURS OF OPERATION, TRAFFIC GENERATION, LIGHTING, NOISE, ODOR, DUST
AND OTHER EXTERNAL IMPACTS**

Applicant's Response: *"Yes."*

This area includes industrial buildings, detached residences and public park space. Communication towers have a unique form and function. Additional traffic and activity are limited to periodic maintenance once a tower is constructed. Operational characteristics of a tower are not directly comparable to daily activity generated by residential and commercial/industrial uses and activities. This application includes a natural gas generator to be located in the shelter building. The proposed use will not generate odor or dust if approved. Regular noise associated with the use is limited to the equipment used for cooling the electrical components within the shelter building, similar to an air conditioner, and periodic maintenance of the generator, also located within the shelter building.

Lighting is not proposed for the tower and is not typically required for towers less than 200 feet tall. Lighting for any security purposes required at the base of the tower is proposed over doorways.

The proposed tower is 120' located in the rear of the property and separated from the recreation path by existing vegetation. The overall height of the tower mitigates the need for the tower to be lit. The proposed tower type is a monopole tower that provides a minimized profile for the type of use compared to other types of tower structures.

Staff Finding – The proposed tower is compatible with the adjacent uses in terms of hours of operation, orientation, and size. A self-supporting monopole tower has the most reduced profile of any tower type other than a fully stealth structure that is disguised as some other type of structure.

**3. WHETHER THE PROPOSED USE WILL CAUSE SUBSTANTIAL DIMINUTION IN
VALUE OF OTHER PROPERTY IN THE NEIGHBORHOOD IN WHICH IT IS TO BE
LOCATED**

Applicant's Response: *"No."*

The Development Code indicates a preference for communication towers to be located in commercial and industrial zoning districts. The tower is located on the western edge of the Brook Creek Neighborhood. Within the neighborhood a small area located between Haskell Avenue and the Burroughs Creek recreation path is zoned and developed with industrial uses. The proposed tower will be located in this portion of the neighborhood to mitigate any impacts to the area. Additionally the tower is sited in the rear of the property. This provides a natural screening of the base station equipment from the public street. The property immediately to the north is an undeveloped residential lot. There is no anticipated diminution of value to this area that will result from the proposed use.

Staff Finding – There is no anticipated diminution of value to this area that will result from the proposed use.

**4. WHETHER PUBLIC SAFETY, TRANSPORTATION AND UTILITY FACILITIES AND
SERVICES WILL BE AVAILABLE TO SERVE THE SUBJECT PROPERTY WHILE
MAINTAINING SUFFICIENT LEVELS OF SERVICE FOR EXISTING DEVELOPMENT**

The proposed tower is located on private property and does not require public infrastructure services such as water and sanitary sewer. There is an existing sanitary sewer line located on the north side of the building. Staff has noted that the location of the tower cannot encroach into the

existing easement. Other infrastructure needs such as telephone, electric and gas service, if needed for a generator, will be accommodated from existing utilities in the area. Westar noted that additional clarification regarding the utility easement is needed for them to serve the proposed tower. The applicant has been notified of this concern and will continue to work with Westar to secure the necessary easements to the site.

Staff Finding – The subject property is located within an urbanized area of the community with adequate public services available to the site.

5. WHETHER ADEQUATE ASSURANCES OF CONTINUING MAINTENANCE HAVE BEEN PROVIDED

The proposed request provides an enforceable tool to address the use and continued maintenance of the property with regard to landscaping, exterior activity, and off-street parking. A requirement of the Development Code is that if a tower is not used for a period of three years than the tower shall be removed. This requirement is noted on the face of the drawing.

This application is for the construction of a communication tower. The approval does not change or alter the existing land use.

Staff Finding – Adequate assurances of continued maintenance are provided with this application.

6. WHETHER THE USE WILL CAUSE SIGNIFICANT ADVERSE IMPACTS ON THE NATURAL ENVIRONMENT

Applicant's Response: *"No."*

The property is located in a developed urban area. The site abuts a natural area along the west property line. This area is part of the Burroughs Creek Linear Park. The existing vegetation west of the rear (west) property line should not be disturbed with the construction of this proposed tower and base station equipment.

The property is not encumbered by the regulatory floodplain.

Staff Finding – No impact on the natural environment is anticipated from the development of this proposed communication tower.

7. WHETHER IT IS APPROPRIATE TO PLACE A TIME LIMIT ON THE PERIOD OF TIME THE PROPOSED USE IS TO BE ALLOWED BY SPECIAL USE PERMIT AND, IF SO, WHAT THAT TIME PERIOD SHOULD BE

Section 20-529 (3) (i) states: *"Any Telecommunications Facility that is not in use for a period of three full years or more shall be removed by the Owner at the Owner's expense. Failure to remove the Telecommunications Facility pursuant to non-use may result in removal and assessment of cost to the property pursuant to K.S.A. 12-6a17."* This code provision limits communication towers to active use. No additional limitation on time is required.

Staff Finding – The Development Code includes a provision for non-use and removal of towers. No additional restriction is needed.

8. NEW TELECOMMUNICATION FACILITIES – ADDITIONAL CRITERIA FOR REVIEW. IN ADDITION TO THE STANDARDS AND CONDITIONS LISTED IN SECTION 20-529

(2) AND 20-529 (9), THE CITY COMMISSION SHALL CONSIDER THE FOLLOWING FACTORS IN DETERMINING WHETHER OR NOT TO ISSUE A SPECIAL USE PERMIT.

(i) Height of proposed Telecommunications Facility.

The proposed height of the tower is 120'. The tower will be capable of supporting a total of three carriers, including Verizon, the applicant.

Tower height and setback are related. The Development Code requires a tower to be "setback from the property line in all directions a distance equal to at least one-half the height of the telecommunications tower if the site is in or adjoins an R Base District." This setback applies to the north property line and requires a minimum setback of 60'. The proposed tower is located 89.3' from the north property line.

In any other abutting zoning district the tower setback is based on an established fall zone for the tower. The specific fall zone of the tower will be provided with the final engineering documentation at the time the tower is ordered for construction. If approved, the applicant will need to provide documentation to demonstrate that in the event of a tower failure the equipment will "fall" within the enclosure area.

Section 20-529 (2)(iv) requires the overall tower height to comply with section 20-302 of the Development Code. Section 20-302 addresses the Airspace Overlay District. The proposed tower is more than 19,000' from the centerline of the Lawrence Municipal Airport Runways. The proposed tower will not impact the Lawrence Municipal Airport.

(ii) Proximity of Telecommunications Facility to residential structures and residential district boundaries.

The nearest residential boundary is the north property line. The proposed tower is 89.3' south of the north property line. The property immediately north of the subject property is vacant. The next nearest residence is approximately 135' north of the proposed tower.

(iii) Technical or engineering requirements limiting placement of the Telecommunications Facility in other areas in order to provide coverage

A requirement for new telecommunications towers is to demonstrate or justify why the proposed equipment cannot be colocated on existing equipment. This requires a third party review. The City contracted with Burns and McDonnell to review the applicant's justification for this request. The third party review concluded there are no structures in the immediate area "suitable for collocation and provide the radio signal coverage proposed by the applicant."

(iv) Nature and uses on adjacent and nearby properties

The proposed site location is the Burroughs Creek Corridor, an existing industrial area. An existing park is located immediately west of the subject property. The following graphic shows the location of the nearest existing residential uses in the immediate area.




Figure 1: Residential Use Locations

(v) Surrounding topography, tree coverage and foliage

The subject property is a developed industrial site. Existing trees are located along the west property line and within the city park boundary. Existing trees are also located on the northeast corner of the property and a single street tree is located on the north side of the entrance drive.

(vi) Design of the Telecommunications Facility, with particular reference to design characteristics that have the effect of reducing or eliminating visual obtrusiveness and making the proposed Telecommunications Tower or Telecommunications antenna a stealth or disguised facility.

The proposed tower is a monopole similar to other telecommunication towers constructed in the city limits on Bob Billings Parkway, Hidden Valley Girl Scout property, and E 23rd Street, Knights of Columbus property. The base station that includes the ground equipment and enclosure is located in the rear of the property behind the existing industrial building.

(vii) Availability of suitable existing Telecommunications towers or other structures for placement of proposed Telecommunications Antenna

Based on the third party review there are no suitable towers or other "tall structures" within the area for co-location of antenna to meet the applicant's requirements. A map included in the Burns and McDonnell report, Attachment 6, shows the locations identified towers and structures considered.

(viii) Whether the character of the proposed site and the proposed Telecommunications Tower will facilitate maximum utilization of space for placement of Telecommunication antennas serving multiple users.

The proposed tower is capable of supporting additional communication carriers as required by the Development Code. The enclosure area is sufficiently large enough to accommodate additional ground mounted equipment to support future carries.

9. STAFF REVIEW

This portion of the staff report addresses the site plan details and physical development of the site. The property is developed with an existing building that was constructed in 1978 according to Douglas County appraisal Records. There is no record of a site plan for this property. Existing site improvements include:

- 2,400 SF building.
- 5,787 SF enclosed exterior storage yard.
- 10,155 SF gravel parking/access drive area.

The existing parking lot area provides access to an overhead door on the abutting property to the south at 1729 Bullene Ave. The access to the site and general interior circulation will be modified by the proposed tower for a portion of the area west of the existing building at 1725 Bullene Ave (subject property). Adequate area for parking and access will be retained.

A. Site Summary/History

A complete site summary is not provided for this application. The request addresses only the communication tower and enclosure area and does not summarize the existing site. There is no existing site plan on this property. The property was developed at a time prior to site planning for industrial buildings. The following site summary is developed from existing city data.

Site Summary: Lot A, Bock 9 of Scott's Replat		
	Existing	Proposed
Lot Size:	27,510 SF	27,510 SF
Building: (SF)		
• Existing warehouse building.	2,400 SF	2,400 SF
• Proposed equipment shelter	0 SF	2,112 SF
• Proposed communication tower		120' tall
Impervious Cover: (SF)	18,569	Unknown
Pervious Cover: (SF) percent	8,941 SF 32.5 %	unknown

Future site development may require a complete site plan of the property including all improvements.

B. Access and Parking

On-site Parking:

Parking is not typically required for communication towers. Maintenance vehicles park within the enclosure as needed for service. Adequate area is provided for vehicle turnaround from the driveway. These structures are accessed for maintenance only. The location of the tower is within an existing industrial site. The location of the tower enclosure occupies a portion of the fenced storage area and rear yard area of the existing site. The parking area is retained on the south side of the building. There is no parking lot striping to indicate the number of spaces and no site plan for the existing improvements. Off-street parking may need to be evaluated for this site in the future with a change of use.

Access: Access to this site is provided via parking lot access from Bullene Drive. The proposed request does not alter the existing driveway location for this property.

C. Design Standards

Site Design:

Historic District Review: This property is not located within the environs of a designated historic property or district.

Pedestrian accessibility: This application is for a utility type use. The tower will be located in the rear of an existing industrially zoned property. Accessibility needs for the site are limited to periodic maintenance of the structure and equipment as needed. The property abuts the Burrough's Creek Trail along the west property line. Existing vegetation separates the tower site from the recreation path.

Neighborhood: This property is located within the Brook Creek Nneighborhood and is adjacent to the Barker Neighborhood. The Woods on 19th Neighborhood is located to the southwest of the subject property. The neighborhoods are connected by the Burrough's Creek Trail and Linear Park.

D. Landscaping and Screening

The following section provides a brief detail of the existing and proposed landscaping for this property. The applicant does not propose to alter the existing landscape condition of the existing site. Generally, the site does not comply with the current design standards for landscaping, street trees, interior landscaping and similar elements. Future development or redevelopment of the site will require

Street Trees: The property was replatted in 1976 as Scott's Replat. A master street tree plan was not required for the property at that time. The site includes one street tree located on the north side of the driveway. Any future street trees will need to account for the overhead lines for species and placement on the site.



Figure 2: Existing Street Trees

Bufferyard: the property abuts residential zoning to the north, and industrial to the west, south and east. A portion of the Burrough's Creek Trail and Linear Park is zoned IL, the same as the subject property. If developed today, Buffering would be required along the north property line.

With regard to the proposed communication tower, ground equipment should be appropriately screened from the residential zoning and the abutting park property. The Park includes mature vegetation along the west property line of the subject property. The proposed improvements are located outside of the existing vegetative boundary. This natural vegetation provides sufficient buffer between the proposed equipment and the public park space.

The property to the north is zoned RS5 (Single-Dwelling Residential) District. The residential property is undeveloped and includes mature vegetation. Staff recommends the site plan be revised to include additional screening be added along the north property line to screen the ground equipment at the base of the tower.

Parking Lot Landscaping: Interior and perimeter landscaping standards were adopted after the development of the site. The parking lot is a gravel surface with no markings to indicate parking stalls. Future development or redevelopment of the site will require appropriate parking lot landscaping. The proposed tower use will not include personnel. Access to the site is limited to occasional maintenance. No off-street parking is required for this use.

Mechanical Equipment Screening: As discussed in the bufferyard section, mechanical equipment is required to be screened per City Code. Screening must be balanced with the need for security and visibility with this type of facility. The provision of landscape material along the north property line provides reasonable screening of the mechanical equipment at the base of the tower without adverse impact on the security of the facility.

E. Lighting

Lighting is not proposed for this tower other than minimum required lighting at the base of the tower for the equipment building. Additional detail regarding the lighting fixture is required to demonstrate compliance with the City's photometric standards.

F. Floodplain

This property is not located within the regulatory floodplain and is not subject to a local floodplain development permit.

G. Other

The "search ring" prepared by the applicant includes The northeast portion of Barker Neighborhood as well as portions of East Lawrence, Brook Creek and all of Willow Woods Neighborhood. Within this area, the predominant use is residential. Options for tower placement are limited in this area.

CONCLUSION

The proposed tower meets the design standards of the Development Code. The proposed tower provides space for future co-location of equipment. Conditions recommended for approval relate to mitigating visual impacts of the proposed tower on the surrounding property owners.



LAWC BARKER
CELL SITE
BULLENE AVENUE
LAWRENCE, KS 66044
DOUGLAS COUNTY

LOCATION No: 273487
PROJECT No: 20130934055

PROPOSED MONOPOLE
WITH COMMUNICATIONS EQUIPMENT

- ANY TELECOMMUNICATIONS FACILITY THAT IS NOT IN USE FOR A PERIOD OF THREE (3) FULL YEARS OR MORE SHALL BE REMOVED BY THE OWNER AT THE OWNERS EXPENSE. FAILURE TO REMOVE THE TELECOMMUNICATIONS FACILITY PURSUANT TO NON-USE MAY RESULT IN REMOVAL AND ASSESSMENT OF COST TO THE PROPERTY PURSUANT TO K.S.A. 12-6a17.
- A SIGN SHALL BE POSTED ON THE FACILITY NOTING THE NAME AND TELEPHONE NUMBER OF THE TOWER OWNER/OPERATOR.
- THE TOWER OWNER/OPERATOR SHALL SUBMIT A LETTER TO THE PLANNING BY JULY 1 EACH YEAR LISTING THE CURRENT USERS AND TYPES OF TELECOMMUNICATION ANTENNA LOCATION ON THE FACILITY.
- THE TOWER WILL BE INSPECTED ANNUALLY AND A REPORT SHALL BE FILED WITH THE DIRECTOR OF PLANNING PER SECTION 20-529 (4) WHICH STATES; INSPECTIONS, ALL TELECOMMUNICATIONS FACILITIES SHALL BE INSPECTED ANNUALLY AT THE OWNER'S EXPENSE AND AN INSPECTION REPORT SHALL BE FILED WITH THE DIRECTOR OF PLANNING. ALL TELECOMMUNICATIONS FACILITIES MAY BE INSPECTED AT ANY TIME BY THE CODES ENFORCEMENT OFFICER IN ORDER TO DETERMINE COMPLIANCE WITH ORIGINAL CONSTRUCTION STANDARDS. DEVIATION FROM THE ORIGINAL CONSTRUCTION FOR WHICH A PERMIT IS OBTAINED CONSTITUTES A VIOLATION OF THIS CODE. NOTICE OF VIOLATIONS WILL BE SENT BY REGISTERED MAIL TO THE TELECOMMUNICATIONS FACILITY OPERATOR WHO WILL HAVE 30 DAYS FROM THE DATE THE NOTIFICATION IS ISSUED TO MAKE ADJUSTMENTS OF REPAIRS. THE OPERATOR SHALL NOTIFY THE CODES ENFORCEMENT OFFICER IN WRITING THAT THE ADJUSTMENTS OR REPAIRS HAVE BEEN MADE BY THE CODES ENFORCEMENT OFFICER TO ASSESS COMPLIANCE. THE OPERATOR SHALL THEN BE NOTIFIED OF THE RESULTS OF THE SECOND INSPECTION. AN APPEAL OF THE DECISION OF THE CODE ENFORCEMENT OFFICER CAN BE MADE TO THE BOARD OF ZONING APPEALS IN ACCORDANCE WITH SECTION 20-1311.
- THE TOWER WILL NOT HAVE TOWER LIGHTING OR BEACONS.



CERTIFICATION:

PRELIMINARY
NOT FOR
CONSTRUCTION

RELEASE	
DATE	
02/25/14	LEASE EXHIBIT
03/19/14	SITE PLAN & TOWER ELEVATION
06/09/14	CONSTRUCTION DWGS - REV A
07/28/14	CONSTRUCTION DWGS - REV B
08/26/14	CONSTRUCTION DWGS - REV C

THIS DRAWING IS COPYRIGHTED AND IS THE SOLE PROPERTY OF THE OWNER. IT IS PRODUCED SOLELY FOR USE BY THE OWNER AND ITS AFFILIATES. REPRODUCTION OR USE OF THIS DRAWING AND/OR THE INFORMATION CONTAINED IN IT IS FORBIDDEN WITHOUT THE WRITTEN PERMISSION OF THE OWNER.

DRAWN BY: CMD
CHECKED BY: DJH

SITE NAME:

LAWC BARKER
CELL SITE

SITE ADDRESS:

BULLENE AVE
LAWRENCE, KS 66044

SHEET TITLE:

PROJECT INFORMATION,
LOCATION MAPS
AND DRAWING INDEX

A&E PROJECT NO.:

001-1507

SHEET NO.:

T-1

APPLICANT
VERIZON WIRELESS
MANAGER-NETWORK REAL ESTATE
PHONE: (913) 244-2800

SITE ACQUISITION

KGI
PHONE: (417) 848-7584

SURVEYOR

HUSKER SURVEYING
PHONE: (402) 423-5202

ARCHITECTURAL AND ENGINEERING FIRM

MAGTECH MIDWEST, INC.
PHONE: (260) 436-2668

POLICE DEPARTMENT
LAWRENCE POLICE DEPT.
111 EAST STREET
LAWRENCE, KS 66044
PHONE: (785) 830-7400

FIRE DEPARTMENT

LAWRENCE FIRE DEPARTMENT
1911 STEWART AVENUE
LAWRENCE, KS 66046
PHONE: (785) 830-7000

PROPERTY OWNER

STEVE L. EUDALY

KANSAS ONE-CALL SYSTEM
811 OR 1-800-DIG SAFE



CONSULTANT TEAM

THE PROJECT INCLUDES:

INSTALLATION OF PANEL ANTENNA, ASSOCIATED COAX AND OTHER EQUIPMENT IN NEW 120' MONOPOLE TOWER.

INSTALLATION OF A 27'-4 1/2"x11'-6" UNMANNED EQUIPMENT SHELTER WITH GENERATOR ON A CONCRETE FOUNDATION.


NEW ELECTRIC AND TELEPHONE/FIBER SERVICE TO SITE AND EQUIPMENT SHELTER. NO WATER SUPPLY OR SEWAGE TO/FROM THE SITE.

SITE LAT/LON ELEV.

LATITUDE - N38° 57' 8.89"
LONGITUDE - W95° 13' 34.91"
GRD ELEV. - ±843.0' AMSL

CONTRACTORS ATTENTION IS CALLED TO EES FOR THIS SITE. SITE HAS RESTRICTIONS ON EXCAVATION/CONSTRUCTION METHODS. STAGE AND STOCKPILING OF EXCAVATED MATERIALS ARE RESTRICTED IN SOME AREAS. AN EROSION PREVENTION AND SEDIMENT CONTROL PLAN IS PART OF THESE PLANS. BEST MANAGEMENT PRACTICES ARE TO BE USED DURING CONSTRUCTION. DIESEL FUEL IS ALSO PROHIBITED AT THE SITE WITH THE EXCEPTION OF FUEL IN THE TANK OF A VEHICLE.

PROJECT DESCRIPTION



VICINITY MAP

MAPS PROVIDED BY DeLORME STREET ATLAS USA



LOCATION MAP

AERIAL MAP PROVIDED BY GOOGLE

ZONING DRAWINGS 8-26-14

DRAWING INDEX

T-1 PROJECT INFORMATION, LOCATION MAPS, AND DRAWING INDEX

SP-1 LAND SURVEY
SP-2 LAND SURVEY

C-1 ENLARGED SITE PLAN
C-2 TOWER ELEVATION AND ANTENNA INFORMATION
C-3 FENCE DETAILS
C-4 EQUIPMENT SHELTER PLAN
C-5 EQUIPMENT SHELTER ELEVATIONS

PARENT PARCEL DESCRIPTION:

Lot A in Block 9 of Scott's Replat of Portions of Blocks 5 and 9 in Homewood Gardens, a Subdivision in the City of Lawrence, Douglas County, Kansas.

PROPOSED LESSEE'S LAND SPACE DESCRIPTION:

That part of Lot A in Block 9 of Scott's Replat of Portions of Blocks 5 and 9 in Homewood Gardens, a Subdivision in the City of Lawrence, Douglas County, Kansas and being more particularly described as follows:

Referring to the Southwest corner of said Lot A, a #4 rebar found for corner; thence northerly on an assumed bearing of North 05°28'03 East, on the westerly line of said Lot A, 54.34 feet; thence easterly North 87°44'19" East, 13.30 feet, to the Point of Beginning for the described Land Space; thence following the perimeter of the described Land Space on the following bearings and distances: North 02°15'41" West, 48.00 feet; thence North 87°44'19" East, 55.00 feet; thence South 02°15'41" East, 23.00 feet; thence North 87°44'19" East, 15.00 feet, thence South 02°15'41" East, 25.00 feet; thence South 87°44'19" West, 70.00 feet, to the Point of Beginning for the described Land Space.

Containing a total calculated area of 3,015 square feet or 0.069 acres, more or less.

LESSEE'S NON-EXCLUSIVE ACCESS/UTILITY RIGHT OF WAY DESCRIPTION:

A Non-Exclusive Access/Utility Right of Way, 25 feet in width, located in that part of Lot A in Block 9 of Scott's Replat of Portions of Blocks 5 and 9 in Homewood Gardens, a Subdivision in the City of Lawrence, Douglas County, Kansas and the centerline being more particularly described as follows:

Referring to the Southwest corner of said Lot A, a #4 rebar found for corner; thence northerly on an assumed bearing of North 05°28'03 East, on the westerly line of said Lot A, 54.34 feet; thence easterly North 87°44'19" East, 13.30 feet, to the Southwest corner of the described Land Space; thence South 02°15'41" East, 12.50 feet, to the Point of Beginning of the centerline for the described Right of Way; thence easterly North 87°44'19" East, 163.07 feet, to a point of intersection on the westerly right-of-way line of Bullene Avenue, also being the Point of Termination for the centerline of the described Right of Way.


Containing a total calculated area of 4,077 square feet or 0.094 acres, more or less.

INFORMATIONAL REPORT:

Based on Commitment for Title Insurance with an effective date of December 3, 2013 provided by First American Title Insurance Company, Commitment No. NCS-643273-KCTY, the following are of survey matters:

9. A Claim and Proof of Ownership recorded March 10, 2009 in Book 1046 at Page 148 concerning the abandoned railroad easement. Does not affect the Land Space and Right of Way.

10. Easements, restrictions and setback lines as per plat, Plat Book 13 at Page 80. Affects Land Space, and shown hereon.



LAND SPACE & R.O.W. DETAIL

Scale: 1"=40'

SURVEYORS NOTES


1.) Generally located in Missouri State Plane Coordinate System, West Zone (NAD-83).

2.) Not a survey of the parent parcel shown, but to be used only for the purposes shown hereon.

3.) The Utility locations shown hereon were determined by observed above ground evidence only. The surveyor was provided with above ground markings to determine any subsurface locations, and makes no guarantee that the underground utilities in the area, either in service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. This surveyor has not physically located the underground utilities.

Zoning Information:
IG: General Industrial

Flood Information:
Property falls within a Zone "X" (Minimal risk areas outside the 1-percent and .2-percent-annual-chance floodplains. No BFEs or base flood depths are shown within these zones) as determined by FEMA Flood Rate Map No. 20045C0178D, effective 8/05/10.



T. 13 S., R. 20 E.
PARENT PARCEL DETAIL

Surveyor's Certificate

I, Jayme M. Malone, a Professional Registered Land Surveyor under the laws of the State of Kansas, certify the above survey was executed by me, on the date shown. Distances shown are measured in feet and decimals of a foot.

Signed this ____ day of _____, 20 ____.

Jayme M. Malone
LS KS #1113

Prepared for:

Prepared for:



Surveyed By:

HS4144




CHECKED BY:

JMM

APPROVED BY:

JMM

#	DATE	DESCRIPTION	INT.
1	1/16/14	80% Prelim	TH
2	2/06/14	Add Land Space/R.O.W.	MG
3	2/26/14	Add Title	MG
4	3/12/14	Comments	TH
5	7/18/14	Lease Area	MG



DATE SIGNED: _____

SITE NAME:

LAWC BARKER

SITE NUMBER:

SITE ADDRESS:

1725 BULLENE AVE.,
LAWRENCE, KS 66044

SHEET NAME:

SITE PLAN

SHEET NUMBER:

SP-1

VICINITY MAP





LEGEND

- = Cor. Fnd
- = Cor. Set 5/8" Rebar
- ⊕ = Section Corner
- Ⓚ = Benchmark
- (M) = Meas. Dist.
- (P) = Plat Dist.
- (D) = Deed Dist.
- (R) = Record Dist.
- P.O.B. = Point of Beginning
- P.O.R. = Point of Reference
- E — = Underground Gas Main
- G — = Underground Telephone
- S — = Underground Sanitary Sewer
- W — = Underground Water Main
- OHP — = Overhead Utilities
- ○ — = Chain Link Fence
- □ — = Wood Fence
- Ⓜ = Air Conditioning Unit
- Ⓢ = Electric Meter
- Ⓢ = Electric Manhole
- Ⓢ = Electric Pedestal
- Ⓢ = Fire Hydrant
- Ⓢ = Gas Manhole
- Ⓢ = Gas Meter
- = Guy Wire
- Ⓢ = Manhole
- Ⓢ = Light Pole
- = Post
- Ⓢ = Power Pole
- Ⓢ = Sanitary Manhole
- Ⓢ = Storm Manhole
- Ⓢ = Telephone Pedestal
- Ⓢ = Telephone Manhole
- Ⓢ = Fiber Optic Marker
- Ⓢ = TV Manhole
- Ⓢ = Valve

The four highlighted dimensions are measurements from center of proposed tower to Eudaly property boundaries

The red dot is the center of the proposed 120 foot monopole tower

LOT A IN BLOCK 9 OF SCOTT'S REPLAT OF PORTIONS OF BLOCKS 5 & 9 IN HOMEWOOD GARDENS



Prepared for:

Prepared for:



Surveyed By:

HS4144




CHECKED BY:

JMM

APPROVED BY:

JMM

#	DATE	DESCRIPTION	INT.
1	1/16/14	80% Prelim	TH
2	2/06/14	Add Land Space/R.O.W.	MG
3	2/26/14	Add Title	MG
4	3/12/14	Comments	TH
5	7/18/14	Lease Area	MG



SITE NAME:

LAWC BARKER

SITE NUMBER:

SITE ADDRESS:

1725 BULLENE AVE.,
LAWRENCE, KS 66044


SHEET NAME:


SITE PLAN

SHEET NUMBER:

SP-2

Existing Tree Line








1 Equipment Shelter Plan

SCALE: 1/4" = 1'-0"

NOTE:
GENERAL CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL EXTERIOR ATTACHMENTS FOR GENERATOR (MUFFLER, VENT, ETC.), DOOR CANOPIES, AND SECURITY LIGHTS



Traverse Section

Equipment Shelter Set Up Procedure

1. INSPECT BUILDING UPON DELIVERY FOR DAMAGE DURING TRANSPORTATION.
2. REMOVE LIFTING BRACKETS FROM SHELTER.
3. ATTACH TIE DOWN BRACKETS TO SHELTER AND FOUNDATION USING ANCHOR BOLTS.
4. INSTALL AND CAULK ALL ACCESSORIES (EXTERIOR LIGHTS, CANOPIES, GENERATOR EXHAUST AND VENT PIPES ETC.)
5. INSPECT ROOF AND ROOF EDGES FOR DAMAGE CAUSED BY OFFLOAD AND REPAIR IF NEEDED.
6. INSTALL BACKER ROD AND CAULK EXTERIOR WALLS AND ROOF.
7. INSTALL FLASHING ON ALL INTERIOR MOD. LINES.
8. MAKE ALL CONDUIT AND CABLE TRAY CROSSOVERS.
9. CLEAN INTERIOR AND COMPLETE ANY TOUCH UP PAINTING AS NEEDED.
10. CHECK DOOR ALARM FOR PROPOER OPERATION.
11. CHECK LIGHTING AND AIR CONDITIONING FOR PROPER OPERATION.
12. INSPECT COMPLETE BUILDING COSMETICS.

Offload Notes

1. BUILDING SHALL BE OFFLOADED LEVEL.
2. ALL CABLES, SHACKLING, SPREADER BARS, ETC. SHALL BE DESIGNED AND SUPPLIED BY OTHERS.
3. ALL LIFTING POINTS SHALL BE USED.
4. 1 1/8" MAXIMUM DIAMETER FOR SHACKLES.
5. REMOVE BRACKET AFTER PLACEMENT OF SHELTER AND INSTALL ANCHOR TIE-DOWN PLATES (SHIPPED LOOSE INSIDE SHELTER) AT EACH LOCATION.
6. OFFLOAD BUILDING WITH CABLES IN VERTICAL POSITION. ANGLED POSITION CABLES ARE NOT ACCEPTABLE.



CERTIFICATION:

FOR REFERENCE ONLY

RELEASE	
DATE	
02/25/14	LEASE EXHIBIT
03/19/14	SITE PLAN & TOWER ELEVATION
06/09/14	CONSTRUCTION DWGS - REV A
07/28/14	CONSTRUCTION DWGS - REV B
08/26/14	CONSTRUCTION DWGS - REV C

THIS DRAWING IS COPYRIGHTED AND IS THE SOLE PROPERTY OF THE OWNER. IT IS PRODUCED SOLELY FOR USE BY THE OWNER AND ITS AFFILIATES. REPRODUCTION OR USE OF THIS DRAWING AND/OR THE INFORMATION CONTAINED IN IT IS FORBIDDEN WITHOUT THE WRITTEN PERMISSION OF THE OWNER.

DRAWN BY: CMD
CHECKED BY: DJH

SITE NAME:

LAWC BARKER
CELL SITE

SITE ADDRESS:

BULLENE AVE
LAWRENCE, KS 66044





SHEET TITLE:

EQUIPMENT SHELTER
PLAN

A&E PROJECT NO.:

001-1507

SHEET NO.:



CERTIFICATION:

FOR REFERENCE
ONLY

[illegible]

THIS DRAWING IS COPYRIGHTED AND IS THE SOLE PROPERTY OF THE OWNER. IT IS PRODUCED SOLELY FOR USE BY THE OWNER AND ITS AFFILIATES. REPRODUCTION OR USE OF THIS DRAWING AND/OR THE INFORMATION CONTAINED IN IT IS FORBIDDEN WITHOUT THE WRITTEN PERMISSION OF THE OWNER.

DRAWN BY: CMD
CHECKED BY: DJH

SITE NAME: _____

LAWC BARKER
CELL SITE

SITE ADDRESS:

BULLENE AVE
LAWRENCE, KS 66044

SHEET TITLE:

EQUIPMENT SHELTER
ELEVATIONS

A&E PROJECT NO.:

001-1507

SHEET NO.:

C-5




Photo Location #4

Photo Location #3

Proposed Tower Location

Photo Location #5

Photo Location #2

Photo Location #1

Photo Location #6

© 2014 Google

Google earth

Imagery Date: 9/18/2011 lat 38.952131° lon -95.225082° elev 849 ft eye alt 3234 ft



Fortune Wireless, Inc.
A Subsidiary of
Fortune Industries, Inc.

Site Name: LAWC Barker
Photo Location #1
Current Looking West from Haskell Ave.





Fortune Wireless, Inc.
A Subsidiary of
Fortune Industries, Inc.

Site Name: LAWC Barker
Photo Location #1
Proposed 120' Monopole
Looking West from Haskell Ave.

Note:
Installation shown is for visual
reference only. Final equipment
& installation may differ.





Fortune Wireless, Inc.
A Subsidiary of
Fortune Industries, Inc.

Site Name: LAWC Barker
Photo Location #2
Current View Looking North from Homewood St.





Fortune Wireless, Inc.
A Subsidiary of
Fortune Industries, Inc.

Site Name: LAWC Barker
Photo Location #2
Proposed 120' Monopole
Looking North from Homewood St.

Note:
Installation shown is for visual
reference only. Final equipment
& installation may differ.





Fortune Wireless, Inc.
A Subsidiary of
Fortune Industries, Inc.

Site Name: LAWC Barker
Photo Location #3
Current View Looking South from Lasalle Ave.





Fortune Wireless, Inc.
A Subsidiary of
Fortune Industries, Inc.

Site Name: LAWC Barker
Photo Location #3
Proposed 120' Monopole
Looking South from Lasalle Ave.

Note:
Installation shown is for visual
reference only. Final equipment
& installation may differ.





Fortune Wireless, Inc.
A Subsidiary of
Fortune Industries, Inc.

Site Names: LAWC Barker
Photo Location #4
Looking South Along Bike / Jogging Trail





This location is the first place along the path where the proposed tower would be visible. It will remain visible while traveling south for approximately 200 feet. Before and after this 200 foot distance the trees on the east side of the path will provide a buffer between the path and the proposed tower.



Fortune Wireless, Inc.
A Subsidiary of
Fortune Industries, Inc.

Site Names: LAWC Barker
Photo Location #4
Proposed 120' Monopole
Looking South Along Bike / Jogging Trail

Note:
Installation shown is for visual
reference nly. Final equipment
& installation may differ.



Verizon LAWC Barker - Photo Location #5 (looking toward proposed tower)
The proposed monopole will not be visible from this spot.




Verizon LAWC Barker - Photo Location #6 (looking north)
The proposed monopole will not be visible from this spot.






1725 Bullene Avenue



Copyright 2011 Esri. All rights reserved. Thu Sep 11 2011

- Red Circle is Extent of Verizon
- Search Area



This coverage improvement combined with the capacity offload will afford our customers the best




Sources: Esri, HERE, DeLorme, TomTom, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), Swisstopo, MapmyIndia, © OpenStreetMap contributors, and the GIS User Community

Legend

- ▲ Tall Structure
- ★ Tower - FCC Registration Numbers




Attachment A Third Party Review LAWC Barker



**SUP-14-00312: Special Use Permit for a New
Verizon Wireless Communications Tower
Located at 1725 Bullene Avenue**

Lawrence-Douglas County Planning Office
November 2014

 Subject Property





Brook Creek Neighborhood Association

Andrea Repinsky, President
1222 Almira Ave., Lawrence KS 66044

Telephone: 913/707-9834

e-mail: brookcreekna@gmail.com; adheron@yahoo.com

November 17, 2014

Bryan Culver, Chair
Lawrence-Douglas County Planning Commission
6 East 6th Street
Lawrence KS 66044

Dear Commissioners:

Brook Creek Neighborhood Association is opposed to the construction of a cell tower at 1725 Bullene. The proposed tower would negatively impact users of the Burroughs Creek Trail and the adjacent residents because of visual disruption, impairment to recreational assets, and negative health impacts.

The Burroughs Creek Trail is an incredibly important recreational and transportation asset to the Brook Creek Neighborhood and the City, one that required tremendous effort on the part of Brook Creek and other neighborhoods to develop. This degree of disruption to the scenic value of the trail is a disservice to the community. The visual impact of the proposed tower was underestimated, as it was assessed while trees were fully in leaf, and the view of the tower location was more obscured than it is now.

Increasing the intensity of the industrial use on the site is inconsistent with the Burroughs Creek Corridor Plan of 2006, which recommends that "when redevelopment of industrially zoned areas is proposed in the future, these areas should be scrutinized for neighborhood compatibility." In no way is a 120-ft tower, located 135 feet from the nearest house, compatible or appropriate to the residential area. In the plan, the site, 1725 Bullene, was recommended to be rezoned from M-1A to C-4. The site should become less industrial, not more.

The staff report neglects to review the full visual impact of a 120-ft tower. Imagine its equivalent, a 10-story building, in order to understand how this tower is entirely inappropriate 135 feet away from a single-family residence. The proposed 6' metal fence, topped with an additional foot of barbed wire, is also inconsistent with the adjacent homes. The applicant's claim that the proposed tower is compatible with adjacent residential uses, and would not diminish the value of these homes, is a claim we do not accept.

Additionally, the health impacts of a microwave radiofrequency radiation (RF) have not been addressed by the City or applicant. The intensity of radiation, and the health effects, are greatest near the transmitter. Multiple studies link RF exposure with genotoxic effects such as gene mutations, cancer, neurological disease such as Alzheimers & Parkinson's, reproductive disorders, and immune dysfunction.

Many questions remain. We doubt the utility of the low elevation site to best serve the purpose of the tower. Very little information was provided to the City and the public about the selection of the small, mostly residential, site search area, and alternate sites or solutions.

Please protect the health and vitality of the neighborhood, and reject the proposed tower.

Andrea Repinsky
President, Brook Creek Neighborhood Association

-----Original Message-----

From: Mary Wharff [<mailto:mgwharff@sunflower.com>]

Sent: Sunday, November 16, 2014 3:47 PM

To: Sandra Day

Subject: cell tower burroughs trail

Please don't build a cell tower near Burroughs Trail or the homes in the area. Burroughs Trail is all about natural environment AND good health — neither of which will be served by a cell tower in the vicinity.

Thanks,

Mary Wharff

1535 Rhode Island St.

Former President, Barker Neighborhood Association