

SYSTEM 7

Conduits							
ID	Existing			Recommendation			Total Cost
	Size	Grade (%)	Q_{cap} (cfs)	Size	Grade (%)	Q_{10yr} (cfs)	
S7-1	30"	2.14	33	30"	2.14	53	\$0
S7-2	18"	0.89	5	30"	0.89	26	\$38,000
S7-3	15"	0.51	3	15"	---	---	---
S7-4	15"	0.86	5	15"	---	---	---
Subtotal Cost =							\$38,000

Note: Dashed entries refer to pieces of the system that are included in GIS mapping, but did not meet the study criteria for having individual analysis in the hydrologic model. Therefore, no recommendation could be given.

Total Cost of System =	\$38,000
-------------------------------	-----------------